



#### FIRE COMPARTMENTATION

- 60 Minute compartment walls to Common Corridor and Flats
- 30 Minute Protected Entrance Lobby

#### PHASES OF WORK

- Cavity Barriers / Fire Stopping installation
- Compartment floor / walls
- Service penetration - All penetrations to be confirmed once services & utilities contractor information is available

#### NOTES

- Cavity barriers (30 minute) in external wall - Vertical @ every party wall, Horizontal @ every party floor to be installed in accordance with ADB Section 9
- Services SVP/RWP's to be fire sealed with collars in accordance with ADB Section 10 Table 14
- Service Risers @ floor slab are not required to be fire stopped on the basis that the partition and doors installed are FD60S rated unless advised otherwise by Building Control
- Allow for fire stopping all services penetration through party walls and floors

CAREYS  
GUN HILL, PRS, ALDERSHOT  
BLOCK A & B - CAVITY BARRIERS-SECTION BB  
DATE  
FEB 2018  
DRAWING NUMBER  
1132-240  
SCALE  
1:50 @ A1  
REVISION  
P1  
STATUS  
INFORMATION

DLA ARCHITECTS PRACTICE  
INTEGRATED ARCHITECTURE  
50 North Thirteenth Street  
CENTRAL MILTON KEYNES, MK9 3BP  
T: 01908 259719 F: 01908 605747  
email: mail@dla-architects.com  
© DLA ARCHITECTS PRACTICE LTD

NOTES  
Do not scale this drawing - use figured dimensions only. All dimensions are to be checked before implementation. Any discrepancies are to be advised immediately. All information is copyright of DLA Architects Practice and may not be used or reproduced without prior permission.

#### REVISIONS