

All Work to Clients & Local Authority Approval.
All Relevant BS's & CP's to be Complied With.
Work Only to Written Dimensions unless directed to scale by Design Team. Report Discrepancy's and Obtain Permission Prior to Proceeding.
Contractor Shall be Responsible to Rectify Any Variations carried out without prior Approval.
Any Disturbance to be Made Good to Match Existing or as Directed. Architraves, Cornices, Doors & Skirtings etc to Match Existing & be Purpose Made where an acceptable standard product is not readily available.
Services to be Altered & Extended as Required.
Materials should comply with the appropriate British Standards and should be marked, stamped, independently certified or otherwise justified by test or calculation to show their suitability.
Workmanship should be in general accordance with BS 8000 series of document and other accepted good practice (ISO 9000)

WINDOWS & EXTERIOR DOORS

Materials for frames, hinges, leaded lights etc to match existing unless a complete new installation is called for. Refer to separate specification. All to be provided with suitable locking devices to match the existing or multi point locking devices complying with insurance industry standards. Easy-clean hinges to be stainless steel types or equal approved with a full opening device where necessary for emergency escape purposes. Glazing to comply with safety glass rules, be double glazed with low-e, anti-glare & Argon fill all incorporated. Maximum gap to sealed units suitable for frame material selected. Obscured glass to be selected by client from samples to be provided by contractor. Leaded lights to include soldered joints where leads cross. Draught stripping to be the best quality fitted into grooves/rebates as applicable. Frames to incorporate a thermal break except where wooden. Obtain Clients written Approval for all details, window/door configuration, leaded light patterns etc prior to placing any orders.

GLAZING ~ SAFETY 1.6 w/m2℃
Any glass in a window within 800mm of floor level or 1500 in a door or within 300mm each side of a door to be Laminated to BS 6206 unless pane of glass is less than 250mm wide and under 0.5sqm in area.

VENTILATION

All habitable rooms to have 1/20th floor area natural ventilation via opening doors or windows to external air with background ventilation of 8000sqmm or 4000sqmm in the case of kitchens, utility rooms, bath or shower rooms. In addition kitchens to have at least a 30L/sec cooker hood ducted to external air or a separate 60L/sec full extract fan. In addition all habitable rooms should have emergency egress consisting of at least a window having an unobstructed openable area of Min 0.33sqm & Min 450mm high or wide the bottom of which should be within 1100 mm of floor level. Mechanical extraction also to be provided as follows:- Utility rooms - 30L/sec, Bath & Shower rooms - 15L/sec. Separate WC's to have a window giving 1/20th floor area & 4000sqmm trickle vent or 6L/sec extract fan. All extract fans to be linked to light switch & with 15 minute overrun unless room has an opening window. 10,000 mm2 trickle vents to all habitable rooms

PIPE & VENT DUCTWORK

Encase all ducts and stack pipes etc in 2 Layers 15mm plasterboard fixed to break joints & with plaster skim finish. 80mm "Gypglas" 1000 sound absorbent quilt infill around pipes etc. 50x50 SW framework. Access panels in 2 Layers 15mm Masterboard or similar fire retardent material screw fixed into min 25mm rebated frame. Low level to stacks.

TIMBER

All to be SC3 (GS,MGS,M50,or M75) grade unless otherwise specified. Structural Engineers details take preference. Roof timbers, any ends to be built into walls or others in a vulnerable location to be treated with a preservative containing a fungicide. Roof timbers to be pressure impregnated with preservative. Spike all doubled joists etc together with 100 mm wires @ 600c/c askew from both sides. Bolt multiple timbers as specified with M12 4.6 black bolts @ 450c/c staggered and with 63mm dia tooth ring plate connectors and washers etc.

STEELWORK

All to be grade 43 to BS 4 Pt 1 & BS 4848 Pts 2&4 painted with 2 coats grey oxide primer after first removing any surface rust etc. Any joints to be bolted or welded to separate detail. 1:2:4 mix concrete or engineering brick padstones to bearings as specified. Structural Engineers details to take preference. Encase steelwork in 2 layers 15mm plasterboard with staggered joints nailed to SW cradles. Plaster skim coat finish to any casing not concealed by other parts of the structure etc. Beams within floor or ceiling voids to have minimum 1 layer of plasterboard in addition to ceiling plasterboard.

LATERAL RESTRAINT

Anchor roofs, ceilings and intermediate floors to external and internal load bearing walls as applicable @ Max 2000c/c. 30x5 galvanized steel straps notched over at least 3No joists, bent as required and extended down walls Min 600mm. Straps to be hooked over inner leaf at intermediate floors or restraint hook joist hangers to be used. Applies to new work in all cases and existing only where directed.

LINTELS

All by specialist manufacturer of best quality. Moisture and rust proofed, factory insulated. (Catnic or equal) Refer to plans for references. Closed end DPC trays over as appropriate. Minimum 150mm end bearings unless otherwise specified. Pre-stressed or normal reinforced concrete may be used over internal openings unless otherwise stated. All to be installed in strict accordance with manufacturers instructions and load/span tables to be complied with. Struct'l Engineers details to take preference.

TIMBER FLOORS

22mm T&G V313 moisture resistant flooring grade chipboard unless otherwise specified screwed to timber joists @ 225c/c & to noggins below all board edges. Refer to section for sizes & c/c of joists & plans for spans. Herringbone strutting at mid span between 2.5m & 4.5m. At 1/3 & 2/3 span if more than 4.5m. Reduce joist c/c by 50% to all bathrooms. Joists to be either built into walls/beams or supported on heavy duty joist hangers. Ceilings to underside of joists where applicable of at least 12.5mm plasterboard & 2.5mm plaster skim coat finish unless other conditions dictate a greater requirement.
If floor is over an open area or adjacent to the ground insulate with 70 mm "Celotex double-R" floor insulation or equal between joists with 25mm air space above supported on Galvanised nails fixed to sides of joists.

STUDWORK PARTITIONS

100x50mm SW studs @ 400c/c. Noggins @ 800c/c. 100x50mm sole & top rails. Double up joists below partitions unless otherwise specified. 12.5mm fireline p/board and 2.5mm skim coat finish both sides with 80mm "Gypglas" 1000 sound insulation quilt infill throughout. All Studwork within a bath or shower room (or other wet area) to be lined out on wet side with ribbed expanded metal lath & 2x10mm coats sand cement render, 1:1:6 mix with waterproof additive.

GROUND FLOORS 0.22 U Value

75mm sand cement screed with chicken wire mesh reinforcement on building paper on 120mm 'Celotex double-R' floor insulation or equal with 25mm strip around perimeter of rooms to prevent cold bridging on 1200 gauge polythene DPM on :-
(a) 150mm thk 1:2:4 mix concrete oversite slab on 150mm layer well consolidated hardcore. Strip all top soil or other deleterious material from site of building. Build up hardcore in layers NE 150mm thk & o/a max 600mm thickness; or
(b) Beam & Block flooring consisting of reinforced concrete inverted 'T' beams by specialist manufacturer & with 100mm 'Celcon Standard' concrete block infill between. Size, spacing & partition supports to manufacturers design & detail. Brush grouted joints after placement. Minimum 150mm vented void below floor beams. Strip all top soil or other deleterious material and cover site of building with 150mm layer of well consolidated clean hardcore. Void to be vented to external air via 215x75 terracotta air bricks @ 900 c/c below DPC level with peroscopic pvc sleeve ducts to link down to inner leaf below floor. Provide apertures in internal walls of at least 1500sqmm/meter run of wall to cross vent to adjacent voids etc. Ensure that air bricks and apertures do not fall below any floor beam bearings or provide concrete lintols to span over. Allow for applied floor finishes to be flush with existing to avoid any steps or ramps unless otherwise specified. In all cases maintain any extg sub floor ventilation providing pvc ducts and additional air bricks as appropriate. Where necessary air bricks to be same size, material and level as any existing ones to property. If foundations 1.5m deep or more then floor type (b) or suspended timber to be used.

DPC's & DPM's

All DPC's to BS 743 Min 150mm above finished ground levels, stepped as required to suit site levels. All on mortar bed. Vertically lap or tank as appropriate. Inner leaf DPC not to be above floor level and to be lapped to floor DPM's. Use Hi-Load DPC's below any concrete floors or floor beams. DPM's to be 1200 gauge polythene or equal approved and protected with soft sand blinding where necessary. All DPC's & DPM's to be lapped to existing at all abutments.

DRAINAGE

All to be to BS 8301. 100mm dia plastic underground drains laid @ 1:40 falls in 150mm pea shingle bed and surround. Min 600mm cover below driveways. Build pipes into walls where passing through with joints within 150mm of wall face and then at approximately 600mm from first joint to form a rocker pipe. All gully's to be roddable back inlet types with fixed covers/gratings. Large radius bends at base of stacks. Provide one way valves to drains or flexible anti-climb fins to stacks to prevent rodents climbing pipes to exit drains. All drains to be accessible and roddable. 450mm dia plastic or 450x450mm brick inspection chambers on 150mm concrete bases. Concrete backfill to plastic IC's. Maximum depth 1.2m. Covers 450mm dia or 430mm sq. All internal IC's etc to be fitted with double seal bolt down air tight covers and frames. Refer to plan for further requirements and/or greater depths etc. All paved area's to be provided with drainage in the form of gully's or channels discharging to a separate surface water drainage system together with rainwater from roofs etc.

BACK DROP MANHOLES

Form back drop connections by dropping vertically outside chamber and enter at channel level to rear or half channel for side entry. Extend main run through chamber wall at incoming invert level and fit screw on cover plate for inspection and cleansing. IC's between 1.2m & 1.5m deep to be 750x675 or 1000 dia with covers same size as chamber. Over 1.5m deep to be 1200x1000 or 1200 dia. Covers 600 sq or dia.

WASTE PLUMBING

All to be to BS 5572. 100mm dia soil & vent stacks or stub stacks as directed. 100mm dia WC branches with 50mm deep 'P' traps. All other traps accessible and cleansable. Waste & trap sizes as follows :- Basins & Bidets 32mm dia, Sinks & Washing Machines etc 40mm dia all with 75mm deep traps. Baths & Showers 40mm dia with 50mm deep traps. No waste to be connected to a stack within 200mm of a WC branch. Increase pipe sizes from 32 to 40mm @ 1.7m, 40 to 50mm @ 3.0m Any wastes over 4.0m provide anti-syphon traps or a vent connected to waste within 300mm of trap, rising continuously either to external air or back to stack above highest flood level. Wherever possible & always at head of drain stacks to be vented to external air via balloon cage 900mm above any ventilation opening within 3.0m. Code 5 lead collars/sleeves above roof abutments. Fresh air inlet valves only to be used in accordance with manufacturers instructions and Local Authority Approval. Provide rodding eyes to all bends & junctions. Box in & conceal wastes etc in agreement with client/owner.

RAINWATER GOODS

All to be in materials/profile to match existing or be agreed with client from samples to be provided by contractor. All to be of an above average depth and at least equivalent to a 115 dia half round section. 63 dia, or equivalent, outlets and down pipes to suit gutter selection. Any choices to be agreed with client. Gutters to be laid to minimal falls towards outlets. Leaf guards and swan neck offsets at eaves. Down pipes to discharge through gulley gratings not over.