

PITCHED ROOFS

Tiles or Slates to match existing or as specified on 25x50 tanalised SW battens @ c/c to give required lap in accordance with manufacturers instructions on 1 layer breathable untearable best quality slaters underfelt to BS 747 on rafters as specified. Ridge, hips, valley's and sprocket eaves etc to match existing where applicable. Valley's to be fully tiled unless otherwise specified. Roof void ventilation at eaves via "Glidevale" or equal approved over fascia vent strips to give at least equal to a continuous 25mm gap. Min 50mm air space to be maintained above insulat'n leading to high level ridge ventilation via matching non conspicuous proprietary tile or ridge vents to give at least equal to continuous 5mm gap. 10mm eaves ventilation only required if no loft rooms.

CEILINGS ~ COLD DECK U Value 0.16

9.5mm Foil backed vapour check plasterboard 2.5mm plaster skim coat finish. (12.5mm plasterboard if also forming part of the underside of a floor or fire protection to steelwork).
100mm Celotex insulation laid between joists to roof voids and a further 50mm Celotex fixed to u/side of joists to eliminate any cold bridge's. Refer to sections for joist sizes & c/c.

FLAT ROOFS ~ COLD DECK 0.18 U Value

Two coat mastic asphalt minimum 20mm thick overall to BS 998 painted with 2 coats white solar reflective paint including all upstands etc. All laid on sheathing felt separating membrane on 19mm marine plywood decking on firings to fall minimum 1 in 40 as indicated on timber joists. Refer to section for sizes & c/c. Spans as indicated. Support joists on heavy duty hangers or build into walls as applicable or on lay boards on rafters. Turn asphalt & decking up 300mm behind roof tiles with tiles dressed down over or provide independent upstands comprising Ex 50x150 tanalised timber with top edge chamfered at 45 degree angle & angle fillet at roof decking level as appropriate. Dress asphalt up and over on expanded metal lathing. Code 5 lead cover flashing over inserted Min 50mm into mortar bed joint, lead wedges and pointed in. DPC cavity trays over as applicable. Ceilings as specified generally. Provide 50mm Celotex to underside of joists insulate between with 120mm Celotex foam board and cross vent roof void on all available sides to at least equivalent of a 25mm continuous air gap with insect screen mesh. Refer to section for details & counter battens etc.

STAIRCASE

Best quality timber to separate specification and to configuration shown. All risers and all goings to be equal as specified on plan. Minimum 50 mm goings to all tapered treads at newels. Goings to tapered treads to be equal at c/c. Minimum 2.0m vertical headroom above nosing line. Handrails to be 900mm above nosing line and landings. Balusters to be vertical and have maximum 99mm gaps between at any point. Refer to plan for overall width string to string. Line underside of stairs with 12.5 mm plasterboard and skim coat finish. Max gradient 42 .

INTERNAL JOINERY

All doors, door linings/frames, architrave's, skirtings, plinth blocks, corner blocks/roundalls, dado rails, window boards, staircase and the like to be purpose made in kiln dried seasoned HW to separate specification. All to be delivered to site only after building is adequately heated and then left to acclimatize prior to fixing. Hidden faces of all joinery to be fixed to walls etc to be sealed to reduce risk of timber being distorted. Doors to be stained to required colour and sealed before leaving manufacturer. A sample door will be required to agree finishes & style before placing final order. Doors to have raised and field panels with bolection mould beading and to be constructed to an equivalent of a FD20 fire rating & a certificate or substantiating details will be required for N.H.B.C. and Local Authority Approval. Frames to be 1/2 hour fire rated but to allow smoke leakage to enable smoke detectors to be activate on hall side of doors (Around 3cum/m/hour. Head & Jambs only). Door between house & garage to be FD30 fire rating with 25x40mm stops glued & screwed to frame. Any glazing required in doors to be "Pyro" fire resisting glass with insulation properties or equal approved. Allow for supply and fitting of best quality hinges (1.5 pairs/door), 3 lever latch/locks (All keyed alike), privacy set locks, ratchet &/or flush bolts as applicable. 5 lever lock and a night latch lock to internal garage door. Allow for fitting only of lever/lock handles supplied by client.

ELECTRICAL INSTALLATIONS

All electrical work will be designed, installed, inspected and tested in accordance with the requirements of BS7671, the IEE 17th edition Wiring Guidance and Building Regulation Part P (electrical safety) by a competent person registered with an electrical self-certification scheme authorised by the Secretary of State. AND the competent person is to send to the Local Authority a self certification certificate within 30 days of the electrical works completion. The client must receive both a copy of the self-certification certificate and a BS7671 electrical installation test certificate.

75% of all new fittings to be low energy
any light fitting penetrating ceiling finishes or any fire resistant surface is to be a fire rated fitting or to have fire resistant hoods fitted

Part G

the wholesome water is coming from the existing water supply from the mains.

Provision must be made by the installation of fittings and fixed appliances that use water efficiently for prevention of undue consumption of water e.g washing machine, dish washer fitted with control use of water. The WC flush system should have a dual push button: one for half tank flush and one for full tank flush.

hot water supply from the combi boiler. Any storage vessel will have 2 independent safety devices such as those that release pressure and so prevent the temperature of the stored water at any time exceeding 100 degrees celcius in addition to any thermostat.

The hot water system has pipework that incorporates a provision for the discharge of hot water from safety devices to be visible at some point and safely conveys it to an appropriate place open to the atmosphere where it will cause no danger to persons in or about the building. fitted with safety devices.

the hot water supply temperature to a bath should be limited to a maximum of 48 degrees celcius to use of an in-line blending valve or other appropriate temperature control device, with a maximum temperature stop and a suitable arrangement of pipework.

FIRE ALARM/ SMOKE DETECTORS =

Smoke detectors to be mains wired to a separate circuit breaker at the consumer control unit and all to be linked for maximum audibility. All to BS 5839 Pt 1 & I.E.E. Regs. Provide to hall, stairs & landing areas within 7.5m of doors to all habitable rooms. If ceiling mounted keep Min 300mm from a wall or light fitting. If wall mounted fit between 150mm to 300mm below ceiling. Keep away from any heating or air conditioning plant or outlets.

Heat detectors to be mains powered with battery back up interlinked and conform to BS5446- 1:2000, or BS5446 2:2003

WALL & FLOOR TILING

All internal wall and floor tiling to be carried out using the appropriate & correct adhesives and grout. Ensure all surfaces are clean, even and flat before commencing. Prepare floors with "Schluter-Ditra" waterproof anti-movement matting and walls with "Schluter-Kerdi" waterproof fibreglass matting or equal approved laid in strict accordance with manufacturers instructions. Ensure that the waterproof layers are lapped and intact before laying any tiles over. Where tiled shower floor bases are required the waterproof layer is to be dressed into an appropriate trapped floor gulley with removable trim to access trap for cleansing. All tile joints to be mitred and plastic edge trim avoided unless agreed beforehand by client. Baths to be filled with water during fixing to walls/floor and whilst tiling. Any specialist tiles/stone/marble to be sealed after fixing in strict accordance with suppliers instructions. All tiling/sanitaryware/taps etc to be properly & thoroughly cleaned after fixing and protected with bubblewrap and hardboard etc taped in position. These areas thereafter to have restricted access. All silicone sealant/beading to be applied by a specialist at the appropriate time with baths filled as appropriate.

BOILERS, HEATING & HW CONTROLS

Boilers to be fueled by Mains natural gas and to have a 'SEDBUK' of at least 92% and to have system controls that switch off the boilers if there is no demand for heating or hot water. Heating system to have zoned controls separate for living and sleeping areas. In large properties no one zone should exceed 150sqm. Each zone for space heating and the hot water system to have separate temperature and time controls. Hot water storage to be in the form of a factory insulated vessel with a minimum 35mm thick coating of PU foam (Min 30kg/cum density) or greater if pressurised including other adjacent equipment. and pipework within 1.0m including vent pipes and primary flow and return to a temperature range of -40 deg C to +700 deg C. All systems to be properly commissioned prior to handover and a report issued together with full operating instructions handed to the client prior to occupation of the building. Boiler flues (fan assisted) to be sited Min 300mm from any openings into the building, 200mm Min below eaves and 150 Min from any drain or soil pipes.
provide Gasafe cert on completion

THE SEPERATING WALLS AND FLOORS WILL BE CONSTRUCTED ACCORDING TO THE APPROVED ROBUST DETAIL IN RELATION TO APPROVED DOCUMENT PART E.

On completion of the installation of a boiler/or hot water storage system, together with associated equipment such as pipework, pumps and controls, the equipment should be commissioned in accordance with the manufacturer's instructions. These instructions will be specific to the particular boiler and/ or hot water storage system.

The installer should give a full expalnation of the system and its operation to the user, including the manufacturer's user manual where provided.

INSULATION OF PIPE, DUCTS AND VESSELS
Reasonable provision would be demonstrate by insulating pipes, ducts and vessels to standars that are not worse than those set out in the Domestic Heating Compliance Guide

On completion of the installation of a boiler/or hot water storage system, together with associated equipment such as pipework, pumps and controls, the equipment should be commissioned in accordance with the manufacturer's instructions. These instructions will be specific to the particular boiler and/ or hot water storage system.

The installer should give a full expalnation of the system and its operation to the user, including the manufacturer's user manual where provided.

Once the installation of a gas-fired boiler is complete the GAS SAFE installer should notify GAS SAFE who will send a Building Regulations Compliance Certificate to the builder, or householder in case of work in an existing dwelling, and notify the building control body on their behalf.

FLAT:
heating via double convector radiator to proposed system combi boiler
92% efficiency.thermostatic valve to each radiator and automatic cut out to the boiler when no heat needed. atleast 300mm away from the window to be discussed on site with the building inspector. Position of the boiler and its flue should be discussed on site with the Gas Safe register person to the building control officer.

the building should be provided with zone, timing and temperature control such that each functional area is independently controlled

emergency lighting to common areas. should be installed according to BS 5266:1
Emergency escape lighting means that part of emergency lighting that provides illumination for teh safety of people leaving an area .

Smoke alarms to all landings. Mains operated with Battery back up and in series.
Heat alarm to kitchen.
Windows to Double glazed and low E coated. 4-16-4.
Toughened to strategic positions.

A fixed temperature heat alarm is used in the kitchen, it activates when the temperature reaches 58°C (136°F).

Internal lightings. The stairwell, main entrances to the block, all common areas should be lit with control switch.

PARAPET WALLS

To be either dense hard brick on edge on double tile crease course or weathered and throated copings to be agreed with client. Samples to be provided for approval. All on DPC on mortar bed with code 5 lead flash -ings as required. To match existing where applicable.

ELECTRICAL INSTALLATIONS
All electrical work will be designed, installed, inspected and tested in accordance with the requirements of BS7671, the IEE 17th edition Wiring Guidance and Building Regulation Part P (electrical safety) by a competent person registered with an electrical self-certification scheme authorised by the Secretary of State. AND the competent person is to send to the Local Authority a self certification certificate within 30 days of the electrical works completion. The client must receive both a copy of the self-certification certificate ans a BS7671 electrical installation test certificate.

Where part M applies see below

The landing call buttons are located between 900mm and 1100mm from the floor of the landing and at least 500mm from any return wall.

wall-mounted socket outlets, telephone points and TV sockets are located between 400mm and 1000mm above the floor, with a preference for the lower end of the range.

Switches for permanently wired appliances are located between 400mm and 1200mm above the floor, unless needed at a higher level for particular appliances.

All switches and controls that require precise hand movements are located between 750mm and 1200mm above the floor

socket outlets are located consistently in relation to doorways and room corners, but in any case no nearer than 350mm from room corners.

lighting pull cords are set between 900mm and 1200mm above the floor level.

TITLE	PROPOSED DRAWINGS	ADDRESS
CLIENT	Mr. C. NORMAN	95 MALVERN ROAD LONDON. NW6
SCALE	1:50 @ A3	
DRAWING NO.	190328/29	
DATE	MARCH 2019	
REV.		