

	Roof Extension and	
	Refurbishment of Three Flats	
	95 Malvern Road London NW6 5PU	
		
	Summary page	
Item	Collection	£
A	Preliminaries	£ 29,508.00
	Full external scaffold @ 2m lifts - provisional sum	£ 17,500.00
	Specifications	
	Schedule of works	£ 12,500.00
	2.0 Enabling works	
	2.1 Asbestos	£ 5,700.00
	3.0 Site set up	Inc
B	BUTTERFLY ROOF	
	4.0 ROOF EXTENSION	£ 48,124.00
	5.0 Rainwater Goods	£ 1,081.00
	6.0 Surface water drains - provisional	£ 2,200.00
C	EXISTING ELEVATIONS	
	7.0 Cleaning brickwork	£ 720.00
	8.0 Brickwork repairs	£ 3,300.00
	9.0 Rear flat roofs	£ 2,000.00
	10.0 Windows	£ 18,484.00
	11.0 External door	£ 500.00
	12.0 Landscape	£ 13,750.00
	13.0 External Decorations	£ 4,120.00
	14.0 Cleaning	Inc

D	INTERNAL REFURBISHMENT	
	15.0 Demolition/ Strip out	£ 6,170.00
	16.0 Structural works	£ 19,643.76
	17.0 Stairs	£ 16,084.00
	18.0 Walls	£ 25,936.00
	19.0 Plaster skim coat	£ 8,260.00
	20.0 New Kitchens	£ 32,784.00
	21.0 Bathrooms	£ 18,860.00
	22.0 Internal Joinery	£ 14,036.00
	23.0 Floor finishes	£ 13,923.00
	24.0 Internal Decorations	£ 10,876.00
	25.0 Window blinds	£ 3,020.00
	26.0 MECHANICAL, ELECTRICAL, WATER DISTRIBUTION & DRAINAGE	
	27.0 Utility Supplies	Excluded
	28.0 Electrical Installations	£ 28,010.00
	29.0 Gas supply	£ 1,890.00
	30.0 Central Heating	£ 13,086.00
	31.0 Cold water distribution	£ 1,222.00
	32.0 Hot water distribution	Inc
	33.0 Drainage	£ 4,546.00
	34.0 Builders work in connection services.	Inc
	35.0 Under ground drains	£ 1,000.00
	36.0 Cleaning	Inc
	37.0 Contingency £15,000	£ 15,000.00
	TOTAL CONTRACT SUM	£ 393,833.76

Exclusions and Clarifications

We have not allowed to upgrade the existing utility incoming supplies. You may want to do this before works begin.

We assume any party wall awards will be granted before we commence works. We do not take responsibility of the condition of existing structures or dealing with 3rd party walls

We exclude any design responsibility for these works.

We require a lead in to commence on site of 6 weeks. This excludes any third party approvals.

We have allowed for the works to be completed in one continuous visit

We require payment every 2 weeks. We will submit valuation every 2 weeks. We request 0% retention is held on every payment. Price excludes VAT

Any changes to the agreed works made by the client may result in additional costs

	Roof Extension and	
	Refurbishment of Three Flats	
	95 Malvern Road London NW6 5PU	
		
		MAG General Building LTD
Item	The Works Description	£
1	SECTION THREE – SCHEDULE OF WORKS	
1.1	Scope of Works	
	The project involves internal refurbishment and roof extension of the existing property from ground to 2nd floor level. <i>The lower ground floor is under separate ownership and excluded from the works.</i> The contractor is to make allowance for the neighbouring properties being fully occupied during the course of the works.	No allowance for LGF made (internal and external)
1.2	General Items	
	This specification describes the requirements, but all the works implied thereby or necessary for the full and proper completion of the Contract is to be performed by the Contractor in the best and most suitable manner even if not particularly referred to herein.	
	The Contractor should note that all items of work contained within this schedule have been described in reasonable detail, but the Contractor shall consider them in conjunction with manufacturers recommendations and actual work on site and shall include in his price for everything necessary to allow him to carry out the works in the best manner, whether specifically mentioned or not.	
	The contractor is to ensure all areas are appropriately secured to prevent access by unauthorised persons for the duration of the contract. The contractor shall provide and locate all welfare facilities and storage compound as required but will ensure written consent from the Local Authority and CA is obtained prior to installation on site.	
	The contractor will provide all materials, plant, labour and expertise necessary to facilitate the successful completion of the works. All materials are to be as specified and used in accordance with all good codes of practice and the manufacturer's recommendations and instructions.	
1.3	Site Rules	
	Note: The following provisions are expressly made: -	
	a. Site rules are primarily to be developed by the Contractor. The Contractor is to ensure that all site operatives are fully aware of the site rules.	
	b. Operational hours are from 0800hrs to 1730hrs Monday to Friday	
	c. The Contractor is to ensure that general rubbish does not accumulate on the site and shall make arrangements for its proper disposal off-site. Compliance with the Control of Asbestos Regulations should be ensured when disposing of any Asbestos Containing Materials.	Asbestos dealt with under below provisional sum
	d. The Contractor should take all necessary precautions to prevent nuisance from noise, smoke, dust, rubbish and any other causes	
	e. All Contractors employees must be signed in and out on a daily basis as part of the Contract requirements.	
	f. Radios, tape players and CD players will not be permitted on site without the express permission of the CA.	
	g. Smoking will not be permitted on site.	
	h. Bonfires or burning of materials and rubbish will not be permitted	
	i. At no point are materials to be stored on neighbouring properties or unlicensed areas.	

	The Contractor is to protect against damage of all features and structures including neighbouring buildings, fences, footpaths, trees etc. The contractor is responsible for making good any damage caused on completion.	
1.4	<i>Temporary Services</i>	
	The Contractor may use the electrical and water supplies currently available on site during the Contract.	
	The Contractor must indemnify the Employer against damage and misuse of the power and water supplies.	
1.5	<i>Person in Charge</i>	
	The contractor is to have a designated site foreman in charge on site to act as a point of contact for all site visitors throughout the project. The person in charge shall not be changed without the permission of the CA, such consent will not to be unreasonably withheld.	
1.6	<i>Health & Safety</i>	
	The Contractor will also be responsible for all aspects of health and safety on the site and the immediate surrounding areas.	
	The Contractor shall take all necessary precautions to ensure that the works are carried out in a safe manner in accordance with their obligations under the Health and Safety at Work Act 1974 and any subsequent Regulations and Rules enacted under this Act.	
	The Contractor shall take all necessary steps to secure the site, or plant, machinery and tools against misuse by unauthorised persons particularly out of working hours.	
	The Contractor is to check the fire evacuation procedures to the existing site/buildings and ensure all fire escape routes are clear at all times.	
	The Contractor is to allow for the provision of all necessary safety equipment to comply with all relevant Health and Safety Regulations. Correct PPE is to be worn at all times and operatives found not wearing such equipment will be asked to leave site by the Contract Administrator.	
	The contractor shall at all times apply the general principles embodied in the Current Construction (Design & Management) Regulations 2015.	
	The works will be notifiable and the contractor shall allow for compliance with the Pre-Construction Information Pack and provision of information necessary for the Construction Phase Health and Safety plan. The contractor shall also allow for providing all information necessary and supplying this to the Principal Designer for inclusion in the file. Allow for keeping a daily site diary and weekly photographs.	
	The contractor should also report any observed defects or otherwise in the construction and services of the sites that may constitute a hazard.	
	Users of special substances should also be aware of and apply the advice contained in COSHH notes.	
1.7	<i>Storage</i>	
	No liability will be accepted for loss or damage to any materials or equipment stored on site. The exact location of site storage and welfare facilities provided by the contractor is to be agreed at the pre-contract meeting.	

1.8	Access	
	Safe access and protection must be afforded at all times by way of scaffolding or otherwise in accordance with all relevant health & safety legislation.	
	The contractor may erect scaffold, temporary towers, ladders, hoists, cranes, protective hoardings, clear sheeting, handrails, etc. to form all necessary working platforms that are required to ensure that all works can be carried out in a safe and workmanlike manner and in accordance with the work at height regulations 2005. The contractor shall allow for compliance with all Scaffolding Regulations, including local authority licences, agreement with neighbours and providing a fully boarded and protected scaffold when erected. The scaffold is to be arranged so the public and occupiers of the property can pass along the pavement and into entrances at ground floor level without restriction and that all access and egress points are maintained and that the fire escape routes are kept clear. Protection to the scaffold shall include all necessary boards and fans to protect all such routes and access ways from any falling materials. Monoflex sheeting is to be fitted to all external elevations of the scaffold.	External scaffold included on summary sheet are provisional sum
	At ground floor level allow for painting all standards white and providing illumination in the hours of darkness in accordance with the Local Authorities recommendations. Include for all necessary spreader boards at the feet of all standards. Confirm with the CA instructions in case of bearing scaffold onto areas of the building above ground floor level. The contractor is to allow for all necessary handrails, perimeter lighting and also plant, tools, tackle and other equipment to comply with statutory recommendations and local authority regulations. Allow for providing all necessary ladders, safety, and security to access all working areas. Out of hours and during public holidays and other periods when scaffold is not in use, including at night and at weekends, the contractor shall remove the bottom ladders and secure to prevent unauthorised access.	
	Contractor to procure any specialist engineering for scaffold at the contractors cost.	
	The contractor shall include for installing an intruder alarm system to the bottom lift of the scaffolding so that it is fully protected when the scaffold is not being worked upon. Allow for installing floodlights to be linked to an infra- red intruder alarm system providing 24 hour monitoring linked to an alarm panel. The alarm must be allowed for detecting out of hours unauthorised access to all zones of the scaffold. The system must be either Permanex or UBX or other similar approved. The contractor shall allow for making the alarm as false alarm free as possible. The alarm will be installed and working once the first lift of scaffolding is erected and even before the lift is boarded or completed, and will not be removed until the bottom lift is to be removed. The contractor shall allow for all necessary alterations to the alarm system	
	The contractor is responsible for arranging and payment of all scaffold licences and ensuring that they are in place before works commence. All licences to last the entire duration of the contract.	
	The contractor is to arrange and pay for any necessary road/ pavement closures and obtain the licences and provide them to the C.A in the event of a request.	
	The contractor to allow to inspect all scaffolding at weekly intervals, or after inclement weather, with competent and authorised scaffolder or suitably trained supervisor, to ensure scaffold is stable and secure, for contract duration. Certificate to be issued to the contractor that scaffolding is stable and secure and to be sent to CA on day of issue.	

	All scaffold fixing points to the building must be made good following completion of the work to the complete satisfaction of the CA.	
PS	Contractor to provide all materials, labour and expertise to provisionally erect a temporary roof to cover 95 Malvern Road, London, NW6 5PU completely while the roof works are undertaken.	£ 12,500.00
1.9	Cleaning	
	On a daily bases, contractor to ensure that all areas of the site, pavement and road are kept free from dirt and debris and cleaned at least once a day.	
	On completion of the works, clean all areas complete leaving clean, tidy and in full working order. Remove all dirt, debris and splashes etc. from all surfaces leaving the area entirely fit for use and to the satisfaction of the CA.	
1.10	Waste and Debris	
	The contractor shall allow to remove all rubbish and debris and other arising's from site as and when necessary and dispose in accordance with any relevant legislation.	
	Provide all skips, licences and waste facilities as required for the removal of all waste throughout the project. Skips are to be the responsibility of the contractor.	
1.11	Pricing	
	Every item in this specification is to be included and indicating a price for that item. Any item not priced will be considered as being included within the tender. It is strongly recommended that the contractor inspects site prior to submitting costs.	
1.12	Samples	
	The contractor is to provide samples of all items as requested in the Schedule for approval by the Contract Administrator.	
1.13	Programme	
	The contractor shall provide a programme of works to the CA prior to commencement of the project showing all stages and timescales for each work item. The contractors tender price is to remain open and valid for that period of time should he be appointed as the successful Principal Contractor. Allow for a 12 months defect liability period.	
1.14	Welfare/ site accommodation	
	The contractor is to provide site accommodation as required in order to undertake the works in a responsible manner in accordance with the Health & Safety Regulations.	
	Total Carried to Collection Sheet	£ 12,500.00
2.0	Enabling works	
2.1	Asbestos	
	Contractor to allow for undertaking a Refurbishment and Demolition Asbestos Survey prior to the works taking place. Once the results are obtained, a copy is to be sent to the C.A immediately.	£ 700.00
	P.S allowed to encapsulate/ remove asbestos containing materials.	£ 5,000.00
	Total Carried to Collection Sheet	£ 5,700.00
3.0	Site set up	
	Carefully disconnect electric, gas, water and waste supplies as necessary leaving all safe to facilitate the works.	Inc
	Provide temporary electrical supply as necessary to facilitate the works.	Inc

	Total Carried to Collection Sheet	£ -
4.0	ROOF EXTENSION	
4.1	Strip out/ demolition	
	Contractor to carefully remove the existing roof rafters, ridges, roof coverings where shown on drawings including, but not limited to felt, sarking, underlay, slates/ tiles/ asbestos cement sheets, battens, insulation, box gutters, leadwork, flashing, and dispose from site immediately.	£ 1,660.00
	Allow to remove 2nd floor structure and entirety including joists, noggins, floor boards and fixing etc. and dispose off site.	£ 1,060.00
	Allow to complete work in stages and agree with C.A onsite.	Inc
4.2	Party Wall	
	Where shown on drawings, contractor to provide all materials, labour and expertise to extend the party wall in reclaimed London stock brickwork in a Flemish bond (Header/ Stretcher Bond) and bonded with sand and cement mortar to form new walls as shown on contract drawings. All mortar to be Class 4 mortar to BS 5628-3:2001.	£ 3,770.00
	Brick colour to match sound existing and samples of bricks to be provided to CA for approval prior to installation. Point brickwork with matching joints to that of the existing building.	Inc
	For supply of bricks allow Prime Cost sum of £1500 per 1000 for supply only.	Inc
	Allow to form appropriate movement joints within walls where new walls exceed 6.0m in length. Exact locations to be confirmed onsite and at returns where possible.	Inc
	At roof level, provide all materials, labour and expertise to supply and fix 30mm x 5mm galvanised metal straps at maximum 2m centres fixed back to a minimum of 3 joists and built in to brickwork.	Inc
	Prepare the new parapet wall above new roof covering, dubbing out as necessary to receive new contractor supplied and installed DPC. Thereafter, contractor to supply and install new twice struck concrete coping stone with drip grooves, bedded on sand cement mortar and thereafter point all joints with polysulphide mastic leaving all sound on completion.	£ 2,772.00
4.3	New 2nd floor structure	
	In location shown on drawings, contractor to reduce the 2nd floor structure in height to provide sufficient head room in 2nd floor space and provide all materials, labour and expertise to supply and fix 50 x 220 x C24 soft wood floor joists at 400 centres with timber solid noggins at supports at 1.8 m centres in locations shown on general arrangement drawings.	£ 3,030.00
	Floor joists to be supported on Simpson Strong Tie, or similar approved, galvanised steel joist hangers or built into external walls.	Inc
	Leave ready to receive floating floor and ceiling treatment as detailed below.	Inc
4.4	New rafters	
	Where walls plates have been removed, Contractor to supply and install 50 x 175 x C24 tanalised softwood wall plate to the face of the new external brickwork wall as illustrated on drawings. Fix wall plate with resin anchored M12 140mm bolts at staggered 300mm centres.	£ 760.00

	Where shown on drawings, contractor to supply and install 50 x 125 C16 tanalised rafters at 400mm centres with birdsmouth seatings at supports. Allow to supply and fix solid strutting at mid span. Make allowance for Dormer window and Velux room lights with double trimmers and rafters around.	£	3,420.00
4.5	Insulation		
	Contractor to supply and install 100mm Celotex foil faced PIR thermal insulation board between rafters, supported on clips to maintain a 25mm air gap above the breather membrane. All boards to be butt fixed and with no gaps.	£	4,250.00
	Contractor to supply and install Celotex 50mm insulated plasterboard to the underside of the rafters. Leave ready for plaster skim coat and decoration.	£	3,420.00
4.6	Breather membrane		
	On top of new rafters, supply and install Klobber 'Permo Forte' vapour permeable roof tile underlay, installed strictly in accordance with manufacturer's instructions. Sealed membrane to eaves carrier trim, in turn dressing to gutter. Allow for laps to be minimum 150mm horizontal and 100mm vertical centres with taped joints. At eaves detail on fascia, allow to lay Ruberoid HD150 under felt on a tilting timber fillet. Include for all details around penetrations.	£	1,240.00
4.7	Ventilation		
	Provide and fit a trim lock or similar eaves ventilation system to incorporate eave bird comb filler fitted to eaves in accordance with manufacturer's recommendations.	Inc	
4.8	Slates covering and lead work		
	Supply and install 25 x 38mm tanalised softwood battens fixed to rafters with 65mm round wire nail at gauge to suit tiles.	£	640.00
	Contractor to provide C.A Marley Eternit Rivendale Fibre Cement Slateslate samples for approval.	Inc	
	Supply and install double lapped Eternit Rivendale Fibre Cement Slates throughout roof in accordance with manufacturers recommendations. Exact lap and size of tile to be agreed onsite. Include for continuous eaves ventilation.	£	9,860.00
	Allow for roof lights as detailed above.	£	810.00
	Provide all materials, labour and expertise and carefully cut chases to external walls as necessary and thereafter introduce new code 4 lead cover flashing at junction of parapet walls and new roof covering, thoroughly lead wedged. All works to be in accordance with best practice and the Lead Associations Guidelines. Stepped flashing to be pointed in same mortar as the remainder of the property.	£	910.00
	Provide all materials, labour and expertise to install lead soakers, lead cover flashings, lead valleys and gutters and the like necessary to waterproof the roof and junctions and in accordance with best practice and the Lead Sheet Association recommendations.	£	576.00
	All leadwork to be installed by current member of the Lead Contractors Association under their 25 year Guarantee Scheme and all work to be complete in accordance with Lead Sheet Association best practice guide lines.	Inc	
4.9	Eaves		
	Provide all materials labour and expertise and install white UPVC fascia and soffit board as detailed on drawings to all elevations, leaving sound on completion.	£	760.00

4.10	Roof pivot Windows (ps)	
PS	Provisionally provide all materials, labour and expertise and carefully install 2 new Fakro Conservation Double Glazed Top Hung Light to sizes shown on drawings, trimmed with double joists in accordance with contract drawings and manufacturers' recommendations.	£ 2,500.00
4.11	Dormer window	
	Contractor to provide all materials, labour and expertise to install dormer windows as per general arrangement drawings.	£ 1,854.00
	Allow for forming the necessary openings within the roof structure and supplying and installing 50 x 100 x C16 timber trimmers, joists, King and Jack studs to form window frames and WBP plywood to form flat roof and cheeks. Join Dormer Rafters to Dormer supports via 2No. M16 Bolted timber connectors and flat plate washers. dormer Rafter support to ridge beam via 2No. M12 Bolts per face.	£ 1,120.00
	Contractor to supply and install 100mm Celotex foil faced PIR thermal insulation board between joists/ rafters and studwork, supported on clips to maintain a 25mm air gap above the breather membrane. All boards to be butt fixed and with no gaps.	Inc above
	Thereafter contractor to supply and install Celotex 35mm insulated plasterboard to the inside face of the joists/ rafters. Leave ready for plaster skim coat and decoration.	Inc above
	For the roof, Contractor to supply and install C24 Grade structural timber firings to roof to provide a minimum of 1:80 fall to comply with part H of Building Regulations.	Inc
	Contractor to supply and install 18mm WBP external ply roof deck to entire Dormer flat roof. Deck to be double nailed to each joist and laid with staggered joints.	Inc above
	Provide all materials, labour and expertise and supply and install new roof covering to Dormer flat roof together with thermal insulation. Include for nailed base layer, vapour barrier, 110mm thick PIR underlay insulation under layer, base layer and cap sheet with grey mineral high performance felt finish providing minimum 15 year insurance back manufacturers Guarantee on completion. Include for UPVC Fascia and ensure that new felt covering has weltd drips over new facia.	£ 1,022.00
	To the cheeks of the Dormer window, supply and install 25 x 38mm tanalised softwood battens with 65mm round wire nail at gauge to suit slates.	Inc above
	Contractor to provide C.A Marley Eternit Rivendale Fibre Cement Slateslate samples for approval.	Inc
	Supply and install double lapped Eternit Rivendale Fibre Cement Slates to Dormer Cheeks in accordance with manufacturers recommendations. Exact lap and size of tile to be agreed onsite. Include for continuous eaves ventilation. Supply and install new lead flashing and soakers to roof junctions in accordance with Lead Sheet Association Guidelines.	Inc above
4.12	Flat roof construction (above new 2nd floor)	
	Contractor to supply and install 50 x 220 x C24 tanalised softwood wall plate wall plate shot blasted into roof steels and fixed to ridges via 5 x 35 x 1000 Galvanized Straps fully nailed.	Inc above

	Between wall plates, contractor to supply and install 50 x 220 C24 tanalised joists at centres birdsmouth seatings at supports. Allow to supply and fix solid strutting at mid span. Include for 47 x 125 C24 Ceiling Collars at 400mm Centres as shown on drawings.	Inc above
	Contractor to supply and install C24 Grade structural timber firings to roof to provide a minimum of 1:80 fall to comply with part H of Building Regulations.	Inc
	Contractor to supply and install 18mm WBP external ply roof deck to entire flat roof. Deck to be double nailed to each joist and laid with staggered joints.	Inc above
	Provide all materials, labour and expertise and supply and install new roof covering to flat roof together with thermal insulation. Include for nailed base layer, vapour barrier, 110mm thick PIR underlay insulation under layer, base layer and cap sheet with grey mineral high performance felt finish providing minimum 15 year insurance back manufacturers Guarantee on completion. Include for all necessary upstands and forming collars as necessary around penetrating flues and pipework etc. and ensure that new chute is watertight and rainwater freely flows in to new rainwater pipework.	£ 2,690.00
	Provide all materials labour and expertise, cut chases as necessary and thereafter introduce new lead cover flashings to weather upstand details to entire perimeter. Allow to point in polysulphide mastic in accordance with manufacturer's recommendations and instructions, leaving all sound on completion.	Inc above
4.13	Loft space	
	Where shown on drawings, contractor to supply and install 300mm insulation quit to roof void along with 100mm Celotex foil faced PIR thermal insulation board between timber studs.	Inc
	Total Carried to Collection Sheet	£ 48,124.00
5.0	Rainwater Goods	
	In locations shown on drawings, provide all materials labour and expertise and supply and fix new half round gutter, 112mm system in Black at roof level allow for all necessary brackets, running outlets, end caps and joints etc. all in accordance with manufacturer's recommendations, leaving all sound and watertight on completion all works to be in accordance with previous specification.	£ 707.00
	Provide all materials labour and expertise and supply and fix 2 no. new rainwater downpipes, 68mm round in Black, to connect to existing underground drainage. Allow for all necessary brackets, joints, back inlet gullies and connecting to underground drainage all in accordance with manufacturer's recommendations, leaving all sound and watertight on completion all works to be in accordance with previous specification.	£ 374.00
	Total Carried to Collection Sheet	£ 1,081.00
6.0	Surface water drains - provisional	
PS	Contractor to provisionally allow to supply and install new proprietary polyprothene inspection chambers 450mm diameter - position to be determined.	£ 2,200.00
	Backfill with pea shingle and form 225mm concrete collar flush with ground. Provide and fit cast iron covers and frames.	Inc in PS

	From new down pipes, supply and install new drainage gulleys and thereafter, excavate below ground and supply and lay new surface water drains in PVC laid to minimum 1 in 60 fall and connect into new inspection chamber and thereafter existing surface water sewer, laid on and surrounded in pea shingle.	Inc in PS
	Total Carried to Collection Sheet	£ 2,200.00
	EXISTING ELEVATIONS	
7.0	Cleaning brickwork	
	Provide all materials labour and expertise and introduce Karcher TFR 10 to all brick surfaces to all elevations complete and thereafter warm pressure wash brickwork removing all dirt and stains leaving all sound on completion in accordance with manufacturers recommendations and instructions.	£ 720.00
	Total Carried to Collection Sheet	£ 720.00
8.0	Brickwork repairs	
PQ	Contractor to supply all materials, labour and expertise to carefully rake out defective, loose and missing mortar and replace with new mortar to match sound existing in sand cement mortar mix 1:1:6 with joint colour and finish to match existing as directed by the Contract Administrator leaving all sound on completion. Allow to repoint 25 Sq. Meters including roof areas, chimney stacks, and all elevations including behind SVP's and downpipes.	£ 650.00
PQ	Contractor to supply all materials, labour and expertise to carefully cut out spalled and defective brickwork and replace with new brickwork to match sound existing in terms of colour, size and texture. Bed and point with a lime mortar to match existing. Allow to replace 50 bricks, including roof areas, chimney stacks, and all elevations including behind SVP's and downpipes.	£ 1,100.00
PQ	Where cracks are present to masonry, contractor to rake out mortar at 450mm vertical spaces, clean and prime slots in mortar beds and bond and bed Helibar, minimum of 500mm each side of crack. Re-point and finish with mortar to match existing. Contractor to provide a Provisional Sum for installation of 25No. Helibars on a piecemeal basis all in accordance with manufacturers recommendations.	£ 1,050.00
	Allow a provisional sum of £500 to repair render to side elevation as directed by C.A.	£ 500.00
	Total Carried to Collection Sheet	£ 3,300.00
9.0	Rear flat roofs	
	Allow a provisional sum of £2,000 to repair to repair 2 flats roofs to rear elevation as directed by C.A.	£ 2,000.00
	Total Carried to Collection Sheet	£ 2,000.00
10.0	Windows	
	Allow for providing necessary protection and thereafter carefully stripping out timber double hung sash windows and boxing frames to all elevations, complete and clearing away all debris from site	Inc

	Supply and install new matching double glazed timber sash windows and box frames to replicate exactly existing window appearance. Include for sash cords and all weight and all matching ironmongery including sash locks, lifts stays and handles etc. to be supplied from Reddiseals - www.reddiseals.com (tel:0845 165 9507) or similar approved. Ironmongery to be approved by C.A prior to ordering and installation. Adapt boxes and reveals as required to accept double glazed sealed units within sashes, and allow for internal making good. Where necessary boxes are to protrude internally within the property and are to be completed with 6mm ply linings and architraves as required. All windows to be fitted with trickle vents.	£	17,544.00
	Sizes of all openings to be checked by the Contractor on site prior to ordering.	Inc	
	Contractor to provide a complete window schedule to C.A for approval prior to ordering windows clearly illustrating sizes and specification.	Inc	
	All new sealed double glazed units to be A rated with air gap in accordance with BS5713, with low E glazing to provide maximum U value of 1.5 with safety glass. All windows to be fitted with trickle vents and glass shall be fitted from the inside. Windows to be fitted in accordance with FENSA recommendations, and 10 year guarantee shall be provided on completion.	Inc	
	To all external joinery, allow for appropriate weathersealing and mastic sealant to perimeter of the opening.	Inc	
	Provide all materials, labour and expertise to supply and fix new bull nosed MDF window boards to all new vertical windows, leaving all sound and tidy, in accordance with previous specification.	Inc	
10.1	Rear 1st floor elevation window		
	Where shown on drawing 190328/15, contractor to reduce the height of the rear window as detailed. Provide appropriately sized Catnic lintel over opening, new brickwork with brick arch to match existing.	£	590.00
	Internally, provide metal railings internally to 1100mm high with max spacing of 99mm.	£	350.00
	Total Carried to Collection Sheet	£	18,484.00
11.0	External door		
	Provisional sum of £500 for repairs to existing external doors to be expended as directed by C.A.	£	500.00
	Total Carried to Collection Sheet	£	500.00
12.0	Landscape		
	Provisional sum of £10,000 for landscaping works to be expended as directed by C.A.	£	10,000.00
12.1	Bike stores		
	In locations shown in attached drawing "Conditions 1", contractor to provide all materials, labour and expertise to supply and install 5No. Single Bike Locker-1 Bike Storage.	£	3,750.00
	Total Carried to Collection Sheet	£	13,750.00
13.0	External Decorations		
	To previously and usually painted timber surfaces allow for preparing and applying two undercoats and one full gloss coat of good quality paint to all areas. All colours to be confirmed.	£	780.00

	To previously and usually painted metalwork allow for rubbing down and preparing and applying one undercoat and one full gloss coat of Hamerite paint. All colours to be confirmed. Where areas of rust are found to existing metal surfaces allow for rubbing back and removing all friable material and applying rust inhibitor before first undercoat.	£	650.00
	To previously and usually painted masonry surfaces allow for rubbing back existing surfaces and preparing and applying two coats good quality masonry pliolite paint to all areas. All colours to be confirmed.	£	2,030.00
	To new timber surfaces (windows) allow for primer, undercoat and one full bodied finishing coat gloss. Colours to be agreed.	£	660.00
	Total Carried to Collection Sheet	£	4,120.00
14.0	Cleaning		
	On completion of the works, contractor thoroughly polish all windows and clean all surfaces and leave clean and tidy.	Inc	
	Total Carried to Collection Sheet	Inc	
	INTERNAL REFURBISHMENT		
15.0	Demolition/ Strip out		
	Provide all materials, labour and expertise and allow stripping out all existing electrical, telecom and media wiring throughout, dispose from site and make good all surfaces disturbed. Allow to provide temporary electrical supply as necessary to facilitate the works.	Inc	
	Provide all materials, labour and expertise and allow stripping out all existing plumbing installations throughout, including SVP's and clear away from site making good all surfaces disturbed. Allow to provide temporary water supply as necessary to facilitate the works.	£	220.00
	Provide all materials, labour and expertise and disconnect all waste supplies, feeds and services as necessary and thereafter strip out kitchens complete together with all cupboards, fridges, freezers and the like and dispose of appropriately from site.	£	330.00
	Carefully strip out all floor coverings including carpet and all skirting and architraves complete and clear away all debris from site.	£	850.00
	Carefully strip out existing radiators and central heating installation and dispose of appropriately from site.	Inc	
	Carefully strip out bath and shower rooms completely together with all sanitary ware, tiling, floor coverings, radiators and the like and clear away all debris from site.	£	925.00
	Carefully strip out doors, windows and frames where shown on drawings to facilitate the works and clear away all debris from site.	£	210.00
	Provide all materials, labour and expertise to remove cupboards, furniture, shelves and the like and clear away from site making good all surfaces disturbed.	Inc	
	Provide all materials, labour and expertise to carefully remove all curtains, nets and blinds and clear away from site.	Inc	
	Carefully hack off tiles to walls and clear away from site.	Inc	
	After demolition, carefully remove all retained wall paper finishes leaving all sound on completion.	Inc	

	Provide all materials, labour and expertise to carefully demolish internal ceilings and dispose of debris and rubble off site.	£ 790.00
	Provide all materials, labour and expertise to carefully lift and dispose of all floor boards and dispose offsite.	£ 830.00
	Provide all materials, labour and expertise to carefully demolish internal walls etc. as shown on drawings and dispose of rubble off site. Allow to temporarily prop and support the remaining walls, floors and ceilings above.	£ 2,015.00
	Allow to remove any other fixtures and fittings left or conduct any other works to facilitate the proposed works.	Inc
	Total Carried to Collection Sheet	£ 6,170.00
16.0	Structural works	
16.1	<i>Openings/ Demolition</i>	
	As per demolition section above, contractor to provide all materials, labour and expertise to demolish walls, chimney breasts and form openings, including windows and doors to achieve the proposed floor plans as per the general arrangement drawings. Remove and dispose of all material immediately from site. Allow to support the above structure with props and leave ready to receive new structural frame.	£ 1,470.00
16.2	<i>Temporary works</i>	
	Contractor to procure and supply all labour, materials and expertise for any temporary works to complete the project and if necessary appoint specialist engineers to design the temporary works. <i>Include for all temporary works cost here including any professional fees. No additions will be entertained onsite.</i>	£ 2,100.00
14.3	Access	
	Allow to shut off the road and pavement as necessary and apply for any necessary licences from the Local Authority.	£ 590.00
	Provide all necessary hoists, cranes and manpower to complete the structural steel works.	Inc
	At no point are materials to be stored on neighbouring properties or areas that contravene Local Authority guidelines.	
16.4	Steelwork	
	Contractor supply all materials, labour and expertise to conduct the works detailed in general arrangement drawings, including but not limited to, forming holes in existing and newly formed walls, installing concrete pads and steel plates, provide the necessary support/ props as required until the new beams are securely installed, installing all beams, plates, posts, bolts, joists, galvanized metal straps etc. in measurements and locations shown on drawings.	£ 14,233.76
	Contractor to allow for all the bolts, connections and connection plates etc. and make due allowance for the design and fabrication of splices to suit preferred method of installation.	Inc
	Contractor to provide a breakdown of cost for all structural works detailed on drawings upon request from the C.A. A full list of structural elements can be found on general arrangement drawings and 190328/30, 31, 32, 33, & 34.	
	Contractor to provide all materials, labour and expertise to fire proof all steel work and provide the necessary 60 min fire resistance.	£ 1,250.00

	Total Carried to Collection Sheet	£ 19,643.76
17.0	Stairs	
17.1	Stairs from first to second floor	
	Contractor to appoint competent joiner to adapt the existing stairs and reduce the height as shown on general arrangement drawings.	£ 2,054.00
	Allow to adopt, supply, install trimmers, trimmings and trimmed joists at landings to facilitate installation ensuring all is level on completion.	Inc
17.2	Fire protection to stairs	
	To the underside of the stairs, supply and fix 2 layers of 15mm with fireline board with tapered edges and ivory face. Tape and fill joints, stop in nail heads and leave ready to receive plaster skim.	£ 650.00
17.3	Floor/ ceiling construction	
	To all floor and ceiling areas (excluding the lower ground floor), contractor to provide all labour, materials and expertise to supply and install new floating floor and ceiling treatment to existing floor joists as shown on drawing	£ 6,330.00
	To the upper ground floor structure, allow to remove existing floor coverings and dispose off site. Thereafter, clean floor void and supply and install Promat 60 Minute SUPALUX Timber Floor system from above. Provide all labour, materials and expertise to supply and install the system to entire upper ground floor including but not limited to 19mm thick T&G chipboard flooring, fillets, ceiling panels and infill all as shown in data sheet in Appendix	£ 7,050.00
	Total Carried to Collection Sheet	£ 16,084.00
18.0	Walls	
18.1	External studwork walls at roof level	
	Contractor to supply and all materials, labour and expertise to build external stud walls as shown in general arrangement drawings. Contractor to supply and construct studwork walls using 50 x 105mm C16 studs at 400mm centres with mid span solid noggins to form the structure shown in general drawings.	£ 2,550.00
	As shown on drawings, contractor to supply and install 18mm wbp external grade plywood to outside face of external studwork walls throughout, leaving ready to receive plasterboard finish.	Inc
	Between the timber studs, contractor to supply and install 100mm Celotex foil backed PIR insulation, tightly packed with a further 50mm of Celotex insulated backed plasterboards internally. Leave ready for plaster skim.	Inc
	To the outer face of the rigid insulation, contractor to supply and fix Tyvek HouseWrap breather membrane, or similar approved, in accordance with manufacturers recommendations.	Inc
	On top of the breather membrane, supply and install 25 x 38mm tanalised softwood battens with 65mm round wire nail at gauge to suit slates.	Inc
	Contractor to provide C.A Marley Eternit Rivendale Fibre Cement Slateslate samples for approval.	Inc
	Supply and install double lapped Eternit Rivendale Fibre Cement Slates to external stud walls in accordance with manufacturers recommendations. Exact lap and size of tile to be agreed onsite. Supply and install new lead flashing and soakers to roof junctions in accordance with Lead Sheet Association Guidelines.	£ 2,950.00
18.2	Internal Wall insulation	

	To the internal face of existing walls, where shown on general arrangement drawings, contractor to provide all materials, labour and expertise to install Xtratherm Thin R internal wall insulation as shown in drawing 190328/23. Leave ready for plaster skim.	£	7,760.00
	Carefully cut chases as necessary and conceal wiring for new electrical installation and thereafter make good prior to plaster skim.	Inc	
18.3	Sound resistant walls (Detail A)		
	Where shown on general arrangement drawings, contractor to provide all materials, labour and expertise to install sound resistant wall as per Details A shown in drawing 190328/21. Leave ready for plaster skim.	£	6,780.00
	Carefully cut chases as necessary and conceal wiring for new electrical installation and thereafter make good prior to plaster skim.	Inc	
18.4	Sound resistant walls (Detail B)		
	Where shown on general arrangement drawings, contractor to provide all materials, labour and expertise to install sound resistant wall as per Details B shown in drawing 190328/22. Leave ready for plaster skim.	Inc	
	Carefully cut chases as necessary and conceal wiring for new electrical installation and thereafter make good prior to plaster skim.	Inc	
18.5	Internal Stud partition walls within flats		
	stud partitions to in locations identified on contract drawings to form internal partitions, structure comprising of 100mm x 50mm softwood studs at 600mm centres with head and sole plates, noggins and filled with 65mm Isover ARP 1200 acoustic insulation between studs. Thereafter supply and fix 12.5mm plasterboard to both sides, joints filled with joint filler and jointing tape leaving all sound on completion and ready to receive skim coat finish.	£	5,896.00
	Within all bathrooms, allow for water resistant plasterboard.	Inc	
	To kitchens and bathrooms, allow to supply and install WBP plywood to timber studwork prior installation of plasterboard.	Inc	
	Carefully cut chases as necessary and conceal wiring for new electrical installation and thereafter make good prior to plaster skim.	Inc	
	Total Carried to Collection Sheet	£	25,936.00
19.0	Plaster skim coat		
	Provide all labour, materials and expertise to supply and apply 'Thistle multi finish' skim coat to all new and existing ceiling and wall surfaces (excluding the proposed ground floor living room) including applying PVA bonding coat where necessary leaving all sound on completion and ready to receive decorations.	£	8,260.00
19.1	Sundry Items		
	Supply and fix corner beads on external angles and plaster reveals square with main walls.	Inc	
	Total Carried to Collection Sheet	£	8,260.00
20.0	New Kitchens		
	Provide all materials labour and expertise and supply and install new mechanical extract fans with humidistat within all kitchens and leave fully operational. Include for ducting where necessary and fitting external grilles and making good as necessary.	£	1,230.00

	Allow the provisional sum of £30,000 (£10,000 per flat) to be used as directed by the Contract Administrator to supply and install new kitchen, including white goods. Allow for extract fan, electric oven and hob pack within integrated installation, ladder unit with integrated fridge freezer, dishwasher and washing machine.	£ 30,000.00
	All installations to be strictly in accordance with manufacturer's recommendations, Best Practice and Building Regulations	
	Contractor to allow to arrange for full design process between client and Manufacturers design team prior to ordering kitchen.	Inc in prov sum
20.1	Tiles	
	Provide all materials, labour and expertise and thoroughly tile all walls within kitchen and above worktops to underside of kitchen units etc., leaving all sound on completion. Include for waterproof grout and adhesive, and applying mastic seals at all corners and junctions with worktops, kitchen units and the like.	£ 1,554.00
	Allow the prime cost sum of £40.00 per meter squared for supply of new tiles and for pricing purposes allow to install 21 Sq.M of wall tiling (7 Sq. M in each flat).	Inc
	Total Carried to Collection Sheet	£ 32,784.00
21.0	Bathrooms	
	Provide all materials labour and expertise and supply and install new mechanical extract fan within bathrooms. Fan to be appropriately rated and incorporate humidistat so as to operate automatically, and leave all sound on completion. Include for ducting where necessary and fitting external grilles and making good as necessary.	£ 2,050.00
	Allow the provisional sum of £13,500 (£4,500 per flat) to be used as directed by the Contract Administrator for the supply and installation of new bathroom fittings.	£ 13,500.00
	Allow to install all drainage and fix strictly in accordance with manufacturers recommendations, connecting to new plumbing/ electrics, leaving all sound and tidy on completion, ensuring all connections are watertight.	£ 820.00
21.1	Tiles	
	Provide all materials, labour and expertise and fully tile all walls within bathroom in accordance with previous specification. Include for waterproof adhesive and waterproof grout and introduce mastic seals at junctions with sanitary fittings in all corners etc. in accordance with previous specification, leaving all sound on completion.	£ 2,490.00
	Allow the prime cost sum of £50.00 per meter squared for supply of new tiles and for pricing purposes allow to install 30 Sq.M of wall tiling (10 Sq. M in each flat).	Inc
	Total Carried to Collection Sheet	£ 18,860.00
22.0	Internal Joinery	
22.1	Skirting boards	
	Provide all labour, materials and expertise to supply and fit 25mm x 200mm moulded softwood skirting boards to all rooms throughout the all flats (except bathrooms), plugged and screwed and stopped.	£ 3,432.00
22.2	Internal doors	

	Provide all materials, labour and expertise to supply and fix 22mm x door width softwood door linings with smoke stops and 19mm x 75 mm chamfered architraves to all internal doors openings.	£	1,654.00
	Provide all labour, materials and expertise to supply and fix new Jeld Wen White Oak Cupboard FD30 Fire doors to all internal door opening including all associated ironmongery. Allow PC sum of £100.00 per door for ironmongery and provide C.A with various options for approval prior to ordering. Include to supply and install intumescent strips and smoke seals to all doors along with Briton brushed steel door closers.	£	6,720.00
	To front entrance doors of Flats, provide all labour, materials and expertise to supply and fix new Jeld Wen White Oak FD60 flush door. Allow PC sum of £150.00 per door for ironmongery and provide C.A with various options for approval prior to ordering. Include to supply and install intumescent strips and smoke seals along with Briton brushed steel door closers and spy hole.	£	1,250.00
	Provide all labour, materials and expertise to supply and fix new Jeld Wen White newbridge Cupboard doors to all internal cupboard doors including all associated ironmongery. Allow PC sum of £100.00 per door for ironmongery and provide C.A with various options for approval prior to ordering.	£	980.00
	Total Carried to Collection Sheet	£	14,036.00
23.0	Floor finishes		
23.1	<i>Barrier matting to front lobby</i>		
	Contractor to supply and lay new heavy contract barrier matting to ground floor lobby as you enter the property. Allow for supply cost of £50 per sq. meter. Colour: TBC. Barrier matting to be laid in accordance with manufacturer's instructions, including underlay, carpet tacks, tackifier and adhesive as required.	£	303.00
23.2	<i>Carpets to communal staircase and ground floor hallway</i>		
	Contractor shall allow for supply and lay new carpet tiles to the staircase including upper ground floor hallway, stairs and landings. Allow for supply cost of £23 per sq. meter. All carpets to be laid in accordance with manufactures instructions, including underlay, carpet tacks, tackifier and adhesive as required. Type and colours to be confirmed.	£	4,260.00
	To new staircases, provide and fit new aluminum nosings in all locations, to be Gradus or similar approved with coloured inserts, colour to be agreed.	£	1,110.00
23.3	<i>Strip wood flooring</i>		
	Provide all materials, labour and expertise and supply and install new strip wood flooring and underlay throughout all flats (except in bedrooms and bathrooms) leaving all sound on completion.	£	5,850.00
	Allow a PC Sum of £50m2 for supply only of flooring	Inc	
23.4	<i>Ceramic tiles</i>		
	To bathroom floors, provide all labour, materials and expertise to supply and fix glazed ceramic tiles fixed with Richafix waterproof Grade 25 adhesive or similar approved, flush pointed with white waterproof epoxy grout with plastic quadrant edging. Include for lining floor beneath with 6mm ply as necessary and leave all sound on completion	£	2,400.00
	Allow a PC Sum of £50 m2 for supply only.	Inc	
	Total Carried to Collection Sheet	£	13,923.00

24.0	Internal Decorations	
24.1	New internal walls	
	One mist and two full coats Dulux trade Diamond Matt emulsion. Colours to be agreed.	£ 6,036.00
24.2	New internal ceiling	
	One mist and two full coats Dulux trade Diamond Matt emulsion. Colours to be agreed.	£ 2,040.00
24.3	New internal timber surfaces	
	Primer, undercoat and two full bodied finishing satin coats. Colours to be agreed.	£ 2,800.00
	Total Carried to Collection Sheet	£ 10,876.00
25.0	Window blinds	
	The contractor shall supply and fit Luxaflex roller blinds in black out fabric to all windows, colour to be agreed. Allow for mounting the blinds to the face of the wall above the windows with all controls mounted on the left of the window.	£ 3,020.00
	Total Carried to Collection Sheet	£ 3,020.00
26.0	MECHANICAL, ELECTRICAL, WATER DISTRIBUTION & DRAINAGE	
26.1	Preambles	
	The contractor shall, supply, install, test and commission a complete drainage, plumbing and mechanical and electrical installation. The Contractor shall assume full responsibility that the works defined in this section and ensure they are correctly undertaken and installation & record drawings / commissioning and maintenance records produced.	
	The contractor is to develop this performance specification into working drawings/ design which comply with current Building Regulations for approval by the C.A before installation. Drawings and specification to be provided in a timely manner and in accordance with Preliminaries to the contract.	Excluded - no design allowed
	The contractor is to provide O&M documentation to include: -	
	Manufacturer's literature and testing & commissioning certification	Inc
	Method of operation, fault-finding procedures, routine maintenance procedures and repair procedures.	Inc
	As-built record drawings	Exc
	The Contractor shall fully test, re-commission (if required) and demonstrate any new installations or modifications to existing installations prior to completion. Unless this has been undertaken then PC will not be issued.	
	Contractor to allow for all builders work in connection with the installations.	Inc
27.0	Utility Supplies	
	The contractor is to contact all the following utility companies and arrange for the following: -	By others
	* New gas connection and meter to each flat. Exact location of meter to be agreed.	By others
	* New electrical connection and meter to each flat and ground floor retail unit. Exact location of meter to be agreed.	By others
	* New water supply and meter to each flat and ground floor retail unit. Exact location of meter to be agreed.	By others
	* New BT/ Internet connection for each flat and ground floor retail unit.	By others

	Contractor to allow for excavations and builders work in connection with new services and include costs for the same here.	Excluded
28.0	Electrical Installations	
	All electrical works to be undertaken by qualified NIC EIC engineer, in strict accordance with the Wiring regulations 17th Edition and tested and certified on completion.	
28.1	General	
	All works and certification must be to the latest edition regulations and to standard BS 7671 Wiring Regulations. These are to be carried out strictly in accordance with the current IEE Wiring Regulations and the relevant Factories Acts.	
	All cabling to be contained within ceiling voids or chased in within the walls; should surface conduit be required then seek CA approval prior to installation. Contractor to visit site at tender stage to check for capacity of existing system and include for any upgrades required including new distribution boards etc. No extras will be entertained for failure to fully assess system and include for all items at tender stage.	
28.2	Electrical installation	
	Provide all materials, labour and expertise and carefully introduce new miniature circuit breaker and thereafter rewire each flat in accordance with general arrangement drawings. Allow for and provide and install the complete small power installation to suit the layout shown on the drawings including fittings, conduit and all accessories. Include for, main powered smoke alarm installation, fuse switch spurs, shaver socket, TV sockets etc.	£ 25,160.00
	Allow for main & supplementary Bonding as required, supplying and fitting energy saving light bulbs throughout house, testing and commissioning and compilation of O & M manuals.	Inc
	Contractor to extend electrical supply from intake and connect it to a new contractor supplied and installed distribution board located in positions shown on general arrangement drawings. Distribution boards shall be manufactured by MEM and sufficient spare ways shall be allocated for future fittings. Distribution boards shall comply with BS EN 60439-1.	Inc
	Fully typed circuit charts shall be provided to permit easy identification of circuits.	Inc
28.3	Small Power	
	The Contractor shall supply, install and connect 13A double switch sockets 450mm above floor levels unless otherwise shown in positions indicated on drawings. Allow for sockets above kitchen worktop.	Inc
	within each flat, include for 4 No. double sockets per room. Allow also for 1 No. BT point and 1 No. telephone socket. Include for fused spurs within kitchen to suit electric oven and hob, new gas fired combination boiler and fit 4 No. worktop sockets in in kitchen and 4 No. skirting mounted sockets to suit new kitchen appliances. Allow for mechanical extract fan within kitchen.	Inc
	All accessories shall be of white plastic and CA approval must be sought prior to installation.	Inc
	Contractor to supply and install all the necessary cables, fixtures and fittings as required ensuring that the plug sockets are fully compliant and operational on completion with necessary commissioning certificates.	Inc
28.4	Internal lighting	

	The contractor to supply and install lighting points /luminaries, switches, etc., as shown on the drawings. Luminaries shall be of low energy type except where indicated. All accessories shall be of the plastic type.	Inc
	Within each flat, include for 4 No. recessed LED halogen lights within kitchen switch by door. 2 No. recessed LED halogen lights entrance lobbys, and 8 No. recessed LED halogen spotlights within each lounge and bedrooms . Allow for 4 No. IP rated recessed spotlights within bathrooms, together with extract fan and shaver point etc. All lights to be switched from the room entrance door.	Inc
	Allow a PC sum of £20 per light fitting.	Inc
	All luminaries shall be installed and connected in accordance with the manufacturer's instructions and switches located as per drawing.	
28.5	Emergency Lighting in stairway	
	The contractor shall design, supply and install new emergency lighting installation to all areas in accordance with BS 5266 pt. 1: 2005 and to building control approval. All emergency lighting shall be provided with local key switches for testing purposes.	Inc
	Luminaires shall be as per Cooper 'Briteblade' range or equivalent.	Inc
	Contractor shall carry out the complete testing, commissioning and demonstration of the emergency lighting system to C.A and Issue fully completed BS 7671 and BS 5266 certification for the entire installation.	Inc
28.6	Fire alarm throughout	
	The contractor shall design, supply and install a new fire alarm installation to provide protection to a minimum of 'L2' as defined in BS5839 to suit the layout shown on the drawings. New system to be installed in strict accordance with current guidelines.	Inc
	The fire alarm system installation shall be analogue addressable. The fire alarm system shall contain multiple loops for detectors, sensors, alarms and output devices and installed to Category L2, as described in BS 5839: Pt 1 + A2:2008.	Inc
	Fire alarm wiring installations shall be installed flush in all occupied areas.	Inc
	Manual call points shall be red finish, mounted in clearly visible locations and positioned to comply with the requirements of BS8300	Inc
	Smoke detectors shall be of the ceiling mounted optical or ionisation detection type and shall be installed complete with interchangeable plug in bases and integral LED's.	Inc
	Heat detectors shall be of the ceiling mounted fixed temperature patterns with rate of rise as required and be installed complete with interchangeable plug-in bases.	Inc
	Sounders shall be of the electronic type capable of providing 93dBA at 1 metre mounted on a suitable flush or surface conduit mounting box and fixed to the ceiling or wall to suit the various areas of the building.	Inc
	Contractor shall carry out the complete testing, commissioning and demonstration of the fire alarm system to C.A and issue certification as detailed in BS 5839 for the entire installation.	Inc

	Allow for the equipment manufacturers to provide full instruction of the complete fire alarm for the client's representatives after the contract completion date. Ensure that the 'as fitted' operating and maintenance manuals and drawings are available at the time of the demonstration and instruction. Provide spare glass and the test keys for the alarm break glass units installed.	Inc
28.7	Earthing and bonding	
	The Contractor shall bond and connect to earth all exposed conductive parts of the electrical installation and all extraneous conductive parts so that in the event of a fault of negligible impedance, disconnection will take place in a manner and in such time as to ensure no danger arises.	Inc
	Contractor shall ensure compliance with BS 7671, BS 7430, BS 6651 and EMC Directive, in particular.	Inc
28.8	Intercom System	
	Provide all materials, labour and expertise and supply and install new video entry system with supply and handsets serving all flats leaving all sound on completion. Allow a PC sum of £500 for supply of video intercom. Contractor to obtain CA approval of intercom system prior to installation.	£ 2,600.00
28.9	Contractor to allow for all builders work in connection with the installations.	Inc
28.10	Telecoms	
	Contractor to supply and install BT network sockets in each flat. Contractor to test and certify installation to EN 50346 and leave fully operational.	Inc
28.11	TV outlet/ Ariel	
	Provide all materials, labour and expertise to supply and install new TV outlets in each flat. Allow for 1 No. socket in each lounge and 1 per Bedroom. Allow to connect to existing Ariel and leave fully operational on completion.	Inc
	Allow a provisional sum of £250 for installation of new communal Ariel.	£ 250.00
	Total Carried to Collection Sheet	£ 28,010.00
29.0	Gas supply	
	Provide all materials, labour and expertise and carefully extend new gas supply in copper pipework to serve new boilers in position as detailed on contract drawings. Works to be completed strictly in accordance with current regulations and best practice. Allow for concealing pipework within boxing, cupboards and voids and cutting chases as necessary.	£ 1,890.00
	Total Carried to Collection Sheet	£ 1,890.00
30.0	Central Heating	
	Provide all labour, materials and expertise to supply and install Valliant gas combi boilers in each flat. Include for Valliant range high efficiency flues and Variable Termination Kits, programmable digital room thermostat. Supply and fit properly sized Stelrad Softline radiators to each room as shown on drawings with TRV's all in accordance with manufacturer's recommendations. Include for towel rail within shower/ bathrooms. Conserve all pipework within floors, ceiling and box in any surface mounted pipework. Leave central heatings fully operational and certified.	£ 11,336.00

30.1	Electric Towel Rack/Radiator in 1st floor bathroom and ensuite	
	The Contractor is to undertake heat loss calculations of the bathroom and ensuite and calculate the size of the electrics towel rails required. Thereafter provide all labour, materials and expertise to supply and fit properly sized electrics towel rails with individual thermostats and timers in location shown on drawing. Allow for all power supplies as detailed above and leave fully operational. Allow a PC sum of £250 for supply only of each radiator.	£ 1,750.00
	Provide all materials, labour and expertise and supply and install new hard wired carbon monoxide monitor adjacent all new boilers in compliance with current regulations.	Inc
	Include to box in all boilers and pipework and include for opening doors.	Inc
	Total Carried to Collection Sheet	£ 13,086.00
31.0	Cold water distribution	
	Provide all labour, materials and expertise to extend new cold water supply to new kitchens, shower/ bathrooms, central heating systems and WC's.	£ 1,222.00
	From new incoming main, carefully extend copper pipework to serve all plumbing and sanitary facilities as detailed on contract drawings and as per current Building Regulations.	Inc
	All distribution pipework shall be concealed wherever possible and exposed pipework shall be kept to a minimum. Any exposed pipework shall incorporate a "chrome" finish.	Inc
	All copper pipework to have soldered joints and are to be connected to individual sanitary appliances with appropriately sized metal sheathed flexible hose in compliance with current water bye laws and building regulations.	Inc
	The new cold water systems shall be designed, installed and tested fully in compliance with BS6700, the New Water Supply Regulations (1999), The WRAS Water Regulations Guide, HSE's Approved Code of Practice and	Inc
	Total Carried to Collection Sheet	£ 1,222.00
32.0	Hot water distribution	
	The contractor shall allow to provide hot water distribution to accommodate the new kitchens, shower/ bathrooms and WC's as shown on drawings.	Inc
	All distribution pipework shall be concealed wherever possible and exposed pipework shall be kept to a minimum. Any exposed pipework shall incorporate a "chrome" finish.	Inc
	Provide all materials, labour and expertise and carefully run new copper pipe work from new boilers to serve all areas. All copper pipework to have soldered joints and are to be connected to individual sanitary appliances with appropriately sized metal sheathed flexible hose in compliance with current water bye laws and building regulations. Include for stop taps and gates valves etc. to isolate each supply and facility including roller ball couplings. All hot water taps to be left fully operational.	Inc

	The new hot water systems shall be designed, installed and tested fully in compliance with BS6700, the New Water Supply Regulations (1999), The WRAS Water Regulations Guide, HSE's Approved Code of Practice and Guidance L8 and CIBSE (TM13 2000) guidance notes for control of Legionella, CIBSE Public Health Engineering Guide G and to meet the requirements of the Local Water Authority Byelaws inspector.	Inc
	Total Carried to Collection Sheet	Inc
33.0	Drainage	
	From all sanitaryware supply and fit all necessary waste pipes, traps, fixtures and fitting etc. and for connection of same to new contractor supplied and installed SVP and underground drainage. All in accordance with current Building Regulations. The systems shall be based upon a simple single stack design philosophy and shall incorporate air admittance valves and/or ventilation to atmosphere in accordance with the requirements of Building Regulations Part H and as defined in BS EN 12056 - Part 2: 2000 utilising the tabulated discharge units in Table 2.	£ 2,080.00
	All new soil and waste pipework shall be concealed behind paneling systems and within service ducts wherever practically possible. Soil and waste pipework shall be in PVC-U pipework with solvent welded joints unless exposed.	£ 1,566.00
	Access /rodding points shall be provided at all new branches, changes of direction and at points of connection into the drainage stacks	Inc
	Where new pipework passes through fire compartment barriers, include for necessary fire sleeves.	Inc
	Include for all necessary excavation, temporary works, sub-base material, pipework, man holes, drain pipes etc. to complete the installation in accordance with current building regulations and obtain the necessary permission from the local water authority to connect into the drains.	£ 900.00
	Where foundations pass over drains, foundations depth shall be increased if necessary, to at least that of the drain and the wall/ foundation carried over pipe on precast concrete lintels of appropriate width, so that no load is transferred to the drain. Provide minimum 50mm clearance to pipe and provide ridged sheet material each side of opening to prevent entry of fill or vermin. Fill void around pipe with compressible sealant to prevent entry of gas.	Excluded
	On completion, leave drainage full operational and constructed in accordance with best practice.	Inc
	Total Carried to Collection Sheet	£ 4,546.00
34.0	Builders work in connection services.	
	Contractor to allow for all associated building works in connection to the services.	
	To all locations where it is not possible to conceal pipework within the fabric of the structure allow to construct 19mm plywood boxing around services, fixed to ex. 25x25mm softwood frame beneath. All boxing to receive British Gypsum "Thistle-Multi" skim finish ready to receive decorations.	Inc
	Total Carried to Collection Sheet	Inc
35.0	Under ground drains	

	Allow the provisional sum of £1,000.00 to be used by the Contract Administrator for repairs to underground drainage installation to facilitate new drainage systems etc.	£ 1,000.00
	Total Carried to Collection Sheet	£ 1,000.00
36.0	Cleaning	
	On completion of the works, appoint professional cleaners clean all areas complete leaving clean, tidy and in full working order. Remove all dirt, debris and splashes etc. from all surfaces leaving the area entirely fit for use and to the satisfaction of the CA.	Inc
	Total Carried to Collection Sheet	Inc
37.0	Contingency	
	Allow the Contingency sum of £15,000.00 to be used as directed by the Contract administrator for additional and unforeseen works as required.	£ 15,000.00
	TOTAL	

Project description	Schedule of Daywork Rates
---------------------	---------------------------

BoQ A	Supplier	Description B	Quant C	unit D	Rate E	Add/omit F
		<u>Daywork Rates</u> Manager/Supervisor - £350 Quantity Surveyor - £320 Planner - £310 Tiler - £250 Carpenter - £270 Labourer - £140 Brickworker - £260 Groundworker - £260 Machine Driver - £280 Non Productive working: Saturday 8am to 5pm 150% Sunday 8am to 4pm 200% Note: Labour rates exclude Supervision Plant cost + 15% Subcontractors cost + 20% Materials cost + 15%	350 320 310 250 270 140 260 260 280			
<u>Clarifications</u>						
<u>Programme Implications</u>						
		Sub Total measured works				
		Total Value £				