

# MASTIC POINTING

## TRADE SPECIFICATION

Careys Civil Engineering  
**EMPLOYERS REQUIREMENTS**  
Gunhill PRS

## SECTION 1 – 1.0 THE WORK

### DESCRIPTION OF THE WORK:

The works comprises: Construction of 107 Dwellings. Refer to accommodation schedule and site plan, together with all site works including the construction of sewers, retaining walls, external lighting, street lighting, paths and paved areas, roads, landscaping, drainage and services and all associated other site works.

This Scope is to be read in conjunction with all tender information issued and subsequent revisions. This Scope will form part of the Sub-Contract. Copies of the drawings, specifications and details are issued with the tender documents.

### WORK COMMENCEMENT:

|                         |                                                                                       |
|-------------------------|---------------------------------------------------------------------------------------|
| Site Start:             |                                                                                       |
| The Build Period to be: |                                                                                       |
| Phasing:                | Phased (ensure that Construction Programming allows required access for occupations). |
| Show Centre:            | Sum to be included for Sales Centre/Fit out.                                          |

## MASTIC POINTING - TRADE SPECIFICATION

### TENDER TO INCLUDE FOR THE FOLLOWING

All surfaces to be cleaned prior to the commencement of the works to ensure no contamination or staining of the sealant colours.

All waste/rubbish materials to be removed from the property at the completion of your works.

All works to be carried out in accordance with the relevant BS.

### Windows

Aluminium windows and doors with the Cavity Frame Fix cavity closer system which will require a white silicone low modulus sealant applied to the head (between the lintel and window) cill and jambs. Sealed internally and grey externally.

No sealant is required between the main roof soffits and either the brickwork/blockwork or windows/lintels.

### External Door Frames

Timber and Aluminium door frames are specified to front, rear and garage personnel doors (no sealant works are required to fire door frames). A white silicone polysulphide sealant is to be applied to the jambs and head (between lintel and frame). Sealed internally and externally.

### Patio Doors

As with windows, follow their technical requirements for the grey colour mastic application, sizes etc. Sealed internally and externally.

### French Doors

As before, follow their technical requirements for the grey colour mastic application, sizes etc. Sealed internally and externally.

### **Porch Canopies**

Mastic Junction of the structure to the wall.

### **Meter Boxes**

A colour matching the finished colour low modulus silicone sealant is required to all four sides.

### **Expansion Joints**

Refer to the Construction Specification for areas of relevant walling to properties and screen walls, etc. Sealant to be 12mm wide x (up to) 25mm deep polysulphide. Expansion joint material ('Filcrete' Polyfoam - or similar) is to be applied beforehand, by the Bricklaying Contractor.

Colour of sealant to match (as near as possible) the finished mortar colour.

Supply linear meter rate for this item as detailed in the tender summary.

### **Internal Sealant Works**

Mastic required internally as follows;

- Kitchen worktops and unit abutments with walls
- All Sanitaryware
- Around all Showers and Enclosures
- All internal corners of tiles and tiled window cills (Incs Floor/wall tile junctions)
- Mastic to perimeter of Vinyl Flooring and laminate flooring
- Mastic to bottom edge of all skirting on external/party walls and internal Blockwork walls