

60 Claremont Park

Scope of Works

TENDER

Read in conjunction with
architectural drawings and
structural engineering
drawings.

GENERAL WORKS

Identification of services: Before starting work check positions of services, where positions are not shown on drawings, obtain relevant details from service authorities, statutory undertakers or other owners (where possible).

Reporting undocumented defects: When discovered immediately give notice. Do not proceed with related work until response has been received.

New drainage system: Manhole at front of house to be moved outside of building footprint. Supply and install new drainage arrangement for rainwater and foul and connect to existing pipework where indicated on the architectural drawings. Contractor to expose existing drainage at early stages to ascertain if proposed drainage design is feasible (refer to the architectural drawings for preferred design detailing). This should be allowed for by the contractor at this stage. BCO to be informed of proposal prior to completing works and the contractor should assess the relationship of the existing/new drainage runs. Contractor to allow for reinstatement of finishes/making good

Mains water supply: Contractor to allow for upgrading existing mains water supply. Include water tap to front of house and rear of the house.

Boiler: Existing boiler to be removed at earliest convenience and system replaced. Megaflo system to be installed (in utility room). Allow for re-locating as identified on the architectural drawings.

Electrics: New smart meter to be installed in utility room, all electrics to be updated in accordance with specification and architectural drawings.

Above ground drainage: Read in conjunction with the architectural drawings. Final design by contractor and approved by building control officer

Structural steel/lintels: Supply and install structural steels/lintels as per structural engineer's drawings and specification.

Partitioning (walls and floors): Timber stud partitions as identified throughout floor plans, including forming openings. Refer to the architectural drawings.

Sound insulation: Install 150mm mineral wool insulation to intermediate floors if required.

Thresholds: Where differing floor finishes meet a threshold strip is to be installed.

Pitched roof: Porch rooftiles to match existing.

Rooflights: See architectural drawings. GRP (fibreglass) on singly ply membrane to be installed in strict accordance with manufacturer's instructions.

Doors: Contractor to liaise with door manufacturers regarding appropriate hinges and linings.

Temporary loft access: Refer to architectural drawings.

Insulation: Thermal plasterboard to all external walls.

Plasterboard: Supply and install 12.5mm Gyproc wallboard to walls as identified in the architectural drawings. Skim and decorate.

Fire rated plasterboard: Supply and install 12.5mm Gyproc fireline to areas indicated in the architectural drawings. Skim and decorate.

Moisture resistant plasterboard: Supply and install 12.5mm Gyproc H Tilebacker plasterboard to walls as identified in the architectural drawings. Skim and decorate.

Bathroom floor: Supply and install Ditra mat to walls and floors within Bathroom, WC and En-Suite.

Finish to window cills externally: Contractor to allow for making good all existing cills and creating new cills and finish in client supplied colour.

Finish to windows internally: Contractor to prepare surface for finish in accordance with manufacturers instructions.

Kitchen: Contractor to prepare area, supplied and install new kitchen. Contractor to prepare services, install appliances and make final connections.

Landscape: Contractor to supply and install sub base for new hard landscaping to the patio. Refer to the architectural drawings, to include retaining wall and steps down to grass. Contractor to install client supplied tiles and to supply all adhesive and grout as identified on the architectural drawings. Contractor to allow for new drainage to comply with the building regulations.

Underfloor heating: Refer to the architectural drawings. In rear open plan space.

Heating system: Supply and install plumbing for new radiators and UFH as indicated on the architectural drawings. Final design by contractor.

Intermittent mechanical ventilation: Refer to the room data sheets. Include for fan isolators and installation of extractor above hob. Allow for boxing in where necessary (refer to the architectural drawings and specification).

Carbon monoxide/smoke/heat detectors: Supply and install mains powered flush mounted carbon monoxide/smoke/heat detectors to comply with the building regulations. Exact locations to be confirmed by client on site. Smart system included

Documentation: All works to be completed by a GAS SAFE registered heating engineer.

Documentation: All works to be completed by a Part P/NICEIC approved electrician. On completion of the works carry out a formal NICEIC approved test of the installation and provide certification and O+M manuals to client.

FABRIC & FINISHES SPECIFICATION

*All painted areas to be prepared and painted in accordance with manufacturers instructions. Colours to be confirmed by client prior to purchasing

Description			Rooms/Element	Supplied	Installed
Ceiling	Type	New FR rated plasterboard and skim prepare for decoration	All	Contractor	Contractor
	Finish	Paint (white Dulux Trade)*	All	Contractor	Contractor
Coving	Type	Contractor to remove all existing	All	Contractor	Contractor
Walls	Type	New FR rated plasterboard and skim prepare for decoration	All	Contractor	Contractor
	Type	Remove Chimney breasts in all rooms	Dining room, living room, master bedroom, bedroom 1, bedroom 3	Contractor	Contractor
	Finish	Paint (white Dulux Trade)*	All	Contractor	Contractor
	Finish	Tiles	Bathrooms lower half, full height in shower	Client	Contractor
Floors	Type	construction	All existing floors	N/A	Contractor
	Type	New extension see specified on drawings. Contractor to insulate and provide floor in accordance with engineering plans	New floors	Contractor	Contractor
	Finish	Laminate/Engineered wood finish	All downstairs (exc. Toilet)	Client	Contractor
	Finish	Laminate/Tiles	Kitchen/living space	Client	Contractor
	Finish	Tiles	Bathrooms	Client	Contractor
	Finish	Basic Flooring	Utility room	Contractor/Client	Contractor
	Finish	Carpet runner	Stair case	Client	Contractor
	Finish	Carpet	All upstairs except bathrooms	Client	Contractor
	Existing	Existing bay windows to be retained and protected throughout the duration of the works	See architectural drawings for location	N/A	Contractor

Windows		Window in Bedroom 3 to switch with smaller window on opposite wall for hall if possible			
	Window move		Bedroom 3/Hall	N/A	Contractor
	New	New double glazed windows	See architectural drawings for location	Contractor/Client	Contractor
	Blinds	Fitted by contractor	All external windows	Client	Contractor
Joinery	Skirting	Plain modern timber skirting		Contractor/Client	Contractor
	Door frame/architraves	New timber around door frames		Contractor/Client	Contractor
	Cills	New timber cills where required	See architectural drawings for location	Contractor	Contractor
	Finish to all new internal woodwork	Paint (white Dulux Trade eggshell)*		Contractor	Contractor
Doors		1 No. timber partially glazed external door			
	Front door		Front door	Client	Contractor
	Pocket	1 No. FD30 rated glass pocket door	Kitchen	Client	Contractor
		Howdens 4 panelled FD30 rated door. Finish paint (white Dulux Trade Eggshell)	All upstairs doors, entrance to utility from kitchen	Contractor/Client	Contractor
	Standard				
	Downstairs	Howdens 4 panelled FD30 rated door with partial glass. Finish paint (white Dulux Trade Eggshell)	From hall to study, dining room (double door) and toilet (frosted glass)	Client	Contractor
	Bifold - external	3 No. aluminium framed glazed bifold doors	From living space to garden	Client	Contractor
	Bifold - internal	4 No. glass FD30 rated bifold door	Living space to dining room	Client	Contractor
	External single rear door	1 No. external utility door (potentially keep existing)	Utility door to garden	Client	Contractor
	External single front door	1 No. external utility door (potentially use existing front door)	Side access utility door	Client	Contractor
Ironmongery		Howdens 4 panelled 35 or 44mm thick door with Eclipse pocket door	En suite bathroom	Client	Contractor
	Type	1+1/2 pair steel ballbearing hinges, latch and lever on rose	All standard doors i.e. not pocket doors	Contractor	Contractor
	Type	Manufacturers specification	All non standard doors	Contractor	Contractor

MECHANICAL & ELECTRICAL SPECIFICATION

** All electrical quantities estimate only. Final layout and numbers to be confirmed with client on site.

Description			Rooms/Element	Supplied	Installed
Lighting	Switches	See architectural drawings for quantity and location (inc. switches for external lights and outside	All	Client/Contractor	Contractor
	Fire rated spotlights	LED MK acoustic and fire rated hoods. See architectural drawings for quantity and location. Lightwave system- smart light monitoring system	All. Smart system everywhere excluding utility room	Client/Contractor	Contractor
	Pendants:	3 No. above kitchen island	Kitchen	Client	Contractor
		1 No. above dining table (not to be fitted just future proof)	Dining room	Contractor	Contractor
	Wall mounted:	3 No. external lights to garden patio and 3 No. to front drive	External front drive & external garden	Contractor	Contractor
		2 No. Above bedside table	Master bedroom	Client	Contractor
Power	Outlets	See architectural drawings for quantity and location	All	Contractor	Contractor
	Spurs	1 for each appliance (inc. TV)	Kitchen, utility room, living room, study	Contractor	Contractor
	USB outlets	2 additional USB sockets as specified on drawings (inc switch in utility room cupboard for hoover)	Include USB in kitchen, study, master bedroom, bedroom 1, utility room	Contractor	Contractor
	External power	Electric vehicle charge point	External front drive	Contractor	Contractor
	Extractor fan	1 No. Venta Axia silent timer	Bathrooms/WC	Contractor	Contractor
	Isolator	1 No. (external to room)	Bathrooms/WC	Contractor	Contractor
	Demister pad	1 No. per bathroom	Ensuite/ Family bathroom	Contractor	Contractor
	Shaver outlet	1 No. per bathroom	Ensuite/ Family bathroom	Contractor	Contractor

Hot Water	Radiators	Modern style radiator. See architectural drawing for quantity and location.	All	Client	Contractor
	Underfloor heating	See architectural drawings for quantity and location	Rear kitchen/living room.	Contractor	Contractor
	Boiler	Megaflow system	Utility room	Contractor	Contractor
	Heating system	Tado/Hive smart thermostat	Hallway	Contractor	Contractor
	Towel rail	Heated towel rail (separate to mains heating)	En suite & Bathroom	Contractor	Contractor
	Heating mat	Electric heat map in bathrooms upstairs	En suite & Bathroom	Contractor	Contractor
Cold Water		Yes	Kitchen, utility room, bathrooms	Contractor	Contractor
		Water tap on outside of porch for watering garden/washing car. Retain water tap to garden.	External front drive/garden	Contractor	Contractor
Communications	Telephone outlets	See architectural drawings for quantity and location	Hallway, Kitchen, Study, Master bedroom, Upstairs hallway	Contractor	Contractor
	Data	2 No. Cat 6 ports in each room + additional for TV (see architectural drawings for location)	All (except bathrooms)	Contractor	Contractor
	Smoke/heat detectors	See architectural drawings for quantity and location	Kitchen, Hallway, Utility Room	Contractor	Contractor
	Security	4 No. Cameras to all external entries	Front drive, side access, bifold garden doors, utility garden door.	Client/Contractor	Contractor
		Smart alarm system (AI)	All	Client/Contractor	Contractor
	TV	Mount bracket and wiring	Living space, Master bedroom, Bedroom 1, Study	Client	Contractor
	Speakers	Bose speakers in ceiling	Kitchen/Living space	Contractor/Client	Contractor

BESPOKE CARPENTRY SPECIFICATION

*** All bespoke carpentry location and design to be agreed with client prior to purchase and installation.

Room	Description	Supplied	Installed
------	-------------	----------	-----------

Porch area	Full height coat cupboard bespoke to fit within porch area. Door mat fitted into floor immediately after front door. Refer to architectural drawings for exact location.	Contractor	Contractor
Hall area	Decorative items to be fitted in hall way e.g. mirrors and photo frames	Client	Contractor
Staircase	Bespoke stairs see architectural drawings. To include carpet runner down middle	Contractor/Client for carpet	Contractor
Kitchen/Living room	New cabinetry/shelving to be supplied and fitted by contractor. Existing furniture to be assembled including: couch, coffee table, TV units, chairs, table. Kitchen to be fitted, see below	Client	Contractor
Dining space	Fit side board unit, shelving	Client	Contractor
Utility space	New cabinetry/shelving to be supplied and fitted by contractor.	Contractor	Contractor
Upstairs Hall area	Build linen walk in closet at end of hall adjacent to Bedroom 3 entrance	Contractor	Contractor
Hall/loft	New ladder access to loft from hall	Contractor	Contractor
Master bedroom	Full height modern style cabinetry fitted wardrobe.	Contractor/Client	Contractor
Bedroom 1/2	Assemble fitted cupboard	Client	Contractor

Utility Room	Splashbacks	Basic	Contractor/Client	Contractor
	Floor mounted, perimeter base units:	Yes	Contractor/Client	Contractor
	Wall mounted units:	Yes	Contractor/Client	Contractor
	Sinks:	1 No.	Contractor/Client	Contractor
	Taps:	1 No.	Contractor/Client	Contractor
	Worktops:	Yes	Contractor/Client	Contractor
	Washing machine	1 No.	Client	Contractor
	Dryer	1 No.	Client	Contractor
	Boiler	1 No.	Contractor/Client	Contractor
	Electric meter	2 Existing meters to be disconnected & removed. New single meter	Contractor	Contractor

Kitchen	Splashbacks	Yes	Client	Contractor
	Floor mounted, perimeter base units:	Yes	Client	Contractor
	Floor mounted, island base units:	Yes	Client	Contractor
	Wall mounted units:	Yes	Client	Contractor
	Sinks:	2 No.	Client	Contractor
	Taps:	2 No.	Client	Contractor
	Worktops:	Yes	Client	Contractor
	Cooker hoods:	1 No.	Client	Contractor
	Dishwashers:	2 No.	Client	Contractor
	Fridge:	1 No.	Client	Contractor
	Freezer:	1 No.	Client	Contractor
	Hobs:	1 No.	Client	Contractor
	Microwave:	1 No.	Client	Contractor
	Ovens:	2 No.	Client	Contractor

WC	Taps:	1 No. mixer taps	Client	Contractor
	Washbasins:	1 No.	Client	Contractor
	WC's:	1 No.	Client	Contractor
	Mirrors:	1 No. (above sink)	Client	Contractor
	Toilet roll holder	1 No.	Client	Contractor

Ensuite	Taps:	1 No.	Client	Contractor
	Washbasins:	1 No.	Client	Contractor
	Shower tray, head, valves & enclosure:	1 No.	Client	Contractor
	WC:	1 No.	Client	Contractor
	Mirror:	1 No. double length	Client	Contractor
	Cupboards	Above and below mirror	Client	Contractor
	Toilet roll holder	1 No.	Client	Contractor

Family bathroom	Taps:	1 No.	Client	Contractor
	Washbasins:	1 No.	Client	Contractor
	Bath:	1 No.	Client	Contractor
	WC:	1 No.	Client	Contractor
	Mirror:	1 No. double length	Client	Contractor
	Toilet roll holder	1 No.	Client	Contractor
	Cupboards	Above and below mirror	Client	Contractor

Second shower room	Taps:	1 No.	Client	Contractor
	Washbasins:	1 No.	Client	Contractor
	Shower:	1 No.	Client	Contractor
	WC:	1 No.	Client	Contractor
	Mirror:	1 No. double length	Client	Contractor
	Toilet roll holder	1 No.	Client	Contractor
	Cupboards	Above and below mirror	Client	Contractor